

**High Commission of India
Dar es Salaam**

Installation of PABX system & 40 handsets - Invitation for Tender

The INDIAN HIGH COMMISSION, Dar es Salaam for and on behalf of the President of India invites tender from companies of repute for the following work:

Name of work	Completion time
SUPPLY AND INSTALLATION OF PABX SYSTEM ALONG WITH 40 HANDSETS AND OTHER ITEMS AS DETAILED IN THE SCOPE OF WORK, AT THE NEWLY CONSTRUCTED BUILDING OF THE HIGH COMMISSION OF INDIA AT SHAABAN ROBERT STREET, GARDEN AVENUE, DAR ES SALAAM.	15 calendar days

Detailed scope of Work is attached at Annexure – 1. Tender document supported with prescribed annexure should be submitted in sealed envelope duly subscribed with the name of work etc to the undersigned. The document will be received up to 1500 hrs on 12 December 2016 and will be opened on the same day at 1530 hrs.

Head of Chancery
High Commission of India
82 Kinondoni Road
PO Box 2684, Dar es Salaam
Email: dhc@hcindiatz.org
Tel: +255 22 2669047

Detailed Scope of work

SUPPLY AND INSTALLATION OF PABX SYSTEM AT NEWLY CONSTRUCTED BUILDING OF THE HIGH COMMISSION OF INDIA AT SHAABAN ROBERT STREET, GARDEN AVENUE, DAR ES SALAAM

S. No.	Item	Description	Unit	Qty
1	PABX (Panasonic PBX (TDE 200))	32 Analog/8 Digital/8 Analog Trunk Ports Expandable up to 236 ports	PCS	1
2	Switch Board/Operator Console (KX-DT546)	Digital Console with Wide LCD Display/Mute/Volume control/Headset Jack/Speed Dial Keys	PCS	1
3	Executive Handsets (KX-DT543)	Two Line Executive Digital Phone s/LCD Display/Hands-free/Volume Control	PCS	8
4	Analog Handsets (KXTS 500)	Ordinary Desk Phones	PCS	32
5	24 Port Cat 6 Patch panel		PCS	6
6	Cat 6 UTP Cable		BOX	5
7	Voltage Stabilizer/UPS		PCS	1
8	30 Pair PVC Cable		METERS	200
9	Accessories		LOT	1
10	TTCL Lines Installation		LOT	1
11	Shifting of OLD PBX and Installing at Residences	Panasonic PBX	LOT	1
12	Installation Training to user and administrator		LOT	1

1. Project Timeline

Time line for the Project as follows

Delivery – Immediate

Installation and commissioning – 1 Week